The following is a guideline for recommended spacing for tests:

Up to 600 linear feet	2 tests
Up to 1,000 linear feet	3 tests
Over 1,000 linear feet	1 test approximately every 300 feet
Cul-de-sac up to 600 linear feet	1 test
Cul-de-sac over 600 linear feet	1 test approximately every 300 feet

A test is comprised of a soils moisture test and relative compaction at 0.0 to 0.5 feet and 1.0 to 1.5 feet.

The Contractor shall guarantee all workmanship and materials utilized in the installation for a period of 2 years from the date of acceptance by the Company.

OSHA REGULATIONS

The Contractor shall at all times observe the applicable rules and regulations established by OSHA in the performance of his work under these Specifications.

TRAFFIC CONTROL

Refer to "Work Area Traffic Control Handbook" current edition.

PROTECTION OF WORK AND CLEAN UP

Until the final completion of the work and acceptance thereof by the Company, the Contractor shall care for and maintain all areas affected by his construction. The Contractor shall remove debris, rubbish, and spoils form the site of the work after its completion and prior to acceptance thereof by the Company. No spoils or new material piles are to remain on dedicated streets over night.

All landscaping must be restored to its original condition. Restitution of property damage must be done in a professional and timely manner.

SHUT-DOWNS AND LINE CHARGING

For all shut-downs, a twenty four (24) hour minimum advance notice must be given to the Company Representative whose name and phone number appear on the bid sheet. All shut-downs and line charging must be made by Company personal. Hourly inspection fees will be charged.