EXAMPLE 2:

Requirements:

1. Above Ground
2. Drain Required
3. Protective Enclosure (If Needed)
4. Minimum Clearance 18”
5. Maximum Clearance 36”
6. Adequately Supported and Restrained to Prevent Movement
7. **NOTE: WATER COMPANY RESPOSIBILITY STOPS AT TIE IN POINT TO WATER CO. MAIN LINE i.e.: AT VALVE TAPPED OFF OF MAIN LINE FOR FIRE SERVICE LATERAL. CUSTOMER RESPONSIBILITY STARTS IMMEDIATELY AFTER ABOVE-DESCRIBED VALVE.**