WATER FACILITIES

No pipelines, meters, or any other water facilities shall be installed prior to curbs and gutters.

EXTRA WORK

The Company reserves the right at any time during the progress of the work to require the Contractor to do extra work or to make changes involving more or less labor, materials, or equipment then is contemplated in the contract.

If the extra work required affects an item of work covered by a Contract unit price, and the extra work does not produce a net charge in the original item quantity in excess of 25%, than such work shall be performed at the Contract unit price.

All other extra work shall be performed at cost plus the stated percentage in the bid. Such extra work shall be ordered in writing by the company after accepting an estimate of the cost of such extra work from the contractor.

All materials furnished and all work done shall be in accordance with the Specifications. All work shall be done in thorough, workmanlike manner by persons skilled in their various trades. Material or workmanship not definitely specified, but incidental to a necessary for the work, shall conform to the best commercial practice for the type of work in question.

NOTES

1. Irrigation Pipe Lines:
   Pipe line materials shall be notes on Standard Plans.
   Specifications shall be in accordance with approved
   Company standards. No cast-in-place pipe shall be used.

2. No field machining on AC pipe. If a Contractor does abrasive saw cutting on Asbestos Cement Pipe (ACP)he can be removed immediately from the job and another enlisted to complete the job with all extra work cost being absorbed by the violating Contractor.